

## **Project Team**



**Brooke Green, PCED** ACHD Project Manager



Steve Thieken, PE, PTOE, AICP B&N Project Manager




Molly Loucks, PE B&N Deputy Project Manager

#### **Presentation Outline**

- Project Overview
- ACHD Goals and Concerns
- Review of the planning process
- Initial Concepts
- Review of Alternatives
- Final Recommended Alternative
- Project Lessons Learned
- Current Status of Project

3



#### Purpose and Objectives - ACHD

- Develop a preferred concept-level design of Orchard Street as a Mobility Arterial between Gowen Road and Victory Road
- Complete a NEPA-compliant analysis of roadway design alternatives



BURGESS & NIPLE
Engineers Planners

5

#### **Corridor and Study Components**

- Level 3 bicycle facility as identified in ACHD Bike Master Plan
- Pedestrian facilities
- Compare roundabout and signal options at Orchard/Gowen intersection
- Balance access, traffic flow, and safety
- Maintain and improve local roadway connections



BURGESS & NIPLE

ST3


### Corridor Background and Challenges


- Growth and traffic projections
- Recent construction to the south
- Airport Master Plan
- History previous study/design efforts
- Landfills and abandoned sewer lagoon
- FAA approval needed Environmental Document

7

## Growth is Happening!








#### 2009 Boise Airport Study and Preliminary Design



11


# Environmental and other site issues

- Known hazards in project corridor
  - Landfills
  - Monitoring wells
  - Abandoned sewage lagoons
  - Significant public and private utilities
  - Proximity to airport



#### **FAA NEPA Coordination**


- Coordination with FAA
- Land Exchange
- Determine NEPA Documentation
  - CAT EX vs EA



13


## **Audience Survey**

- Type your thoughts in the chat:
  - What do you envision the biggest issue(s) will be?
  - What should the primary project goals be?




### Stakeholder Advisory Group

- Meeting #1 Listen and learn
  - Introduction to study process
  - Learn about stakeholder needs, ideas, issues, or concerns that the study team should consider
- Meeting #2 Consider options
  - Review initial concepts
  - Discuss advantages and disadvantages for each concept
  - Discuss/suggest changes or refinements to concepts, or additional concepts
  - Listen and learn some more
- Meeting #3 Evaluate options
  - Review draft evaluation matrix and preliminary recommendations
  - Provide feedback and suggest modifications
  - Listen and learn some more



## Major Stakeholders - Concerns

- ACHD
- Airport
- City of Boise
- Gowen Field (Airforce National Guard)
- Knife River
- Valley Regional Transit
- Other Private



#### **Design Concept Development Evaluation**

- Identify Initial Options
- Screen Initial Options
- Create Concepts
- Develop and Evaluate Alternatives
- Refine Alternatives into Conceptual Designs
- Make Recommendations based on final evaluation and implementation considerations


19


### **Design Alternatives Evaluation**


- Potential Criteria (evolved)
  - Traffic operations
  - Non-motorized user performance
  - User safety
  - Design impacts and costs
    - Horizonal
    - Vertical
    - Drainage & Stormwater BMP
    - Right-of-way
  - Environmental impacts
  - Land use/business impacts
  - Others as identified




















**Concept Development** 


#### Concept 1

- Roundabout control at major access points
- Left turn access to properties fronting Orchard St limited to roundabouts
- Limited Access. Limited right-in/right-out only access granted
- Connection to existing Orchard St via Diamond St (north); Dorman St (south)
- Gowen Rd disconnected from existing Orchard Rd and Harvard St
- Gowen Rd realigned
- Harvard St connected to existing Orchard St

29


### Concept 1 - layout






### Concept 2

- Traffic signal control at major access points
- Left turn access properties fronting Orchard St limited to signals
- No additional access granted
- Connection to existing Orchard St via Diamond St (north);
   Aeronca St (south)
- Orchard St cut off north of Harvard St
- Gowen Rd realigned and new "T" intersection with Harvard St





#### Stakeholder Meeting #2

- Reviewed Concepts
- Feedback
  - Like roundabouts for easy left turn access and less delay
  - Concern about access to Gowen Field, Valley Regional Transit, and Airport Parcel
  - Preferred multiuse path vs bike lanes
  - Preferred narrower lanes (closer to 12')

35

#### **Evolution of ACHD Concerns**


- NEPA not the biggest concern
- Oversized Overweight Loads
- Stakeholder Coordination
- Multiple landfills, environmental concerns

Alternative Development


37


## **Project Challenges**


- Existing landfills
- Coordination with partner agencies
- Pedestrian access over New York Canal
- Oversized overweight vehicles
- Boise Airport Runway Protection Zone
- Significant Utilities
- Complex Drainage













#### **Utilities**

- Ten major utilities within project area
- Utilities within the Existing Orchard Street Corridor to remain unless utility owner plans to relocate themselves
- Coordination with City of Boise on Sewer extension/relocation
- Monitoring well relocations
- Potential impacts to Intermountain Gas fire training facility at Dorman






#### Alternative #1

- Four lane Orchard Street with a raised center median
- 10-ft wide shared-use paths
- Pedestrian and cyclist connections between realigned Orchard Street and existing Orchard Street.
- Realigned Gowen Road to provide a curve designed for 40 mph in the vicinity of existing Orchard Street/Harvard Street.
- Full movement intersection at Diamond Street and realigned Orchard Street
- Full movement intersection with realigned Orchard Street at either Dorman Street or Aeronca Street
  - with roundabout control at Dorman Street
  - with the option of roundabout or signal control at Aeronca Street
- Full movement intersection with realigned Orchard Street at Gowen Road with either signalized or roundabout control


47



#### Alternative #2

- Four lane Orchard Street with a raised center median
- 10-ft wide shared-use paths on both sides of realigned Orchard Street and on both sides of Gowen Road between realigned Orchard Street and existing Orchard Street.
- Realigned Gowen Road to provide a curve designed for 40 mph in the vicinity of existing Orchard Street/Harvard Street
- Full movement intersection with realigned Orchard Street at Dorman Street with roundabout control
- Full movement intersection at Diamond Street and realigned Orchard Street Full movement intersection with realigned Orchard Street at Gowen Road with either signalized or roundabout control

49



#### Harvard Street/Gowen Road/Ex. Orchard Street Intersection








Option 3

51


# **Audience Survey**


- Type response in Chat
  - Which alternative do you like best and why?




ternatives	s Cor	mparis	son			
	Alt 1 – Aeronca		Alt 1 – Dorman		Alt 2	
	Signalized	Roundabout	Signalized	Roundabout	Signalized	Roundabout
Traffic Movement/ Efficiency					•	
Traffic Safety					•	
Access to Land/Future Plans					•	
Truck Movement					•	
Bicycle & Pedestrian Mobility					•	
Cost						
Constructability/Risk						
	Al	t 1 – Harvard/Gowen/Exist	ing Orchard			
	Option 1	Option 2	Option 3		Excellent	
Traffic Movement/ Efficience	су 🎒			•	Good	
Traffic Safe	ty 🔴	•			Neutral	
Access to Land/Future Plan	ns 🎒				Fair	
Co	st 😈	0	-		Poor	









**Project Lessons Learned** 

59

# Balancing Project Team/Stakeholder Concerns

- Dynamic team
  - Technical staff, planners, agency/stakeholder representatives
- Stakeholder Concerns
  - One-on-one meetings
- Transitioning PMs
- New Consultant
- Elected Official Buy-in

**Current Project Status** 

61

#### **Current Status**

- Currently in Design (Summer 2020-Fall 2021)
  - Changes since adoption
- Right-of-Way Phase 2022-2023
- Construction to follow Right-of-Way over two years



# Thank You!

Brooke Green – bgreen@achdidaho.org

Steve Thieken – steve.thieken@burgessniple.com

Molly Loucks – molly.loucks@burgessniple.com

BURGESS & NIPLE
Engineers Planners